

PROJECT: Oakview Animal Hospital

LOCATION: Hoover, AL

SIZE: 5,768 SF

PROJECT TYPE: Commercial / Community

GENERAL CONTRACTOR: Williford Orman Construction

ROOF PANELS: Ultra-Lok

WALL PANELS: PBR

OVERVIEW:

Oakview Animal Hospital in Hoover, Alabama features four interconnected steel building sections that integrate with conventional masonry and stud construction. Working with Williford Orman Construction, ACI designed and fabricated the clear span framing, UltraLok standing seam roofing, and select PBR wall panels. The combination of gabled and lean to rooflines gives the 5,768 square foot veterinary facility its distinctive architectural design.

FEATURES:

- Four interconnected building sections with two gabled and two lean to rooflines
- Clear span steel framing integrated with masonry and stud construction
- 24 gauge UltraLok roofing with floating clips and thermal spacers
- Matching metal roofing for the architectural tower's hip roof